



01 / PURPOSE AND SCOPE

Offshore module removal. A basis for the next decision.

Illustrative example of study structure and decision traceability. No client asset, project result or execution approval is represented.

Purpose

Define the information and engineering work needed to compare removal as one unit with removal in engineered sections.

Scope and exclusions

One redundant topsides module, from preparation and separation through transport and receiving handover. Wells, substructure and unrelated systems are excluded from this example.

Decision sought

Agree the verification and study tasks needed before a preferred removal approach is selected.

What this example demonstrates

The scope is held constant. Competing records remain visible. Options are screened against their information needs. Open actions identify who must provide the evidence and when it is required.

No dimensions, loads, durations, costs or acceptance limits are supplied. Project-specific engineering, competent review and applicable approvals remain necessary.



02 / EVIDENCE AND OPTIONS

Make the information gaps explicit.

Illustrative evidence register

Evidence topic	Example position	Decision affected	Next action
Weight and contents	Weight report and modification record do not reconcile	Removal unit size and lifting basis	Reconcile equipment, retained contents and changes
Structural condition	Available information does not establish all temporary states	Support and restraint during separation	Define the states and information needed for engineering review
Isolation boundary	Retained-system interfaces require confirmation	Preparation and separation scope	Reconcile process records with the asset owner's boundary
Receiving route	Acceptance requirements have not been established	Cleaning, packaging, transport and handover	Obtain the intended receiving facility's information requirements

Illustrative options record

Approach	Information needed to assess it	Current conclusion
Removal as one unit	Reconciled weight basis, load path and lifting, transport and landing constraints	Feasibility not established in this example
Removal in engineered sections	Section boundaries, temporary states, access, handling and repeated transfers	Feasibility not established in this example

Both approaches address the same scope and end state. No preferred option or calculated ranking is assigned.



03 / ACTIONS AND NEXT DECISION

Carry the conditions forward.

Illustrative action register

Item	Action	Responsibility to agree	Required by
01	Reconcile weight and configuration	Asset owner with engineering reviewer	Before the options review
02	Define temporary states and study inputs	Appointed engineering team	Before a removal recommendation
03	Confirm isolation and preparation boundaries	Asset owner and operating representatives	Before preparation scope is finalised
04	Establish material acceptance information	Project team and intended receiving facility	Before the material pathway is committed

Next decision

Review the updated evidence and option basis before selecting an approach for further engineering.

The example explains a study process. It does not authorise lifting, removal or demolition work.

Discuss a decision brief for your asset

jed@enduradecom.com / +61 415 963 003

[Explore the offshore and onshore decision walkthrough](#)